

SECTION 01010

PROJECT SUMMARY

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Summary of the Work
- B. Project Time
- C. General Requirements

1.02 SUMMARY OF THE WORK

- A. Work shall consist of approximately 7,185' of 8" DIP gravity sewer including crossings of Highway 43 and the Tennessee Southern Railroad with 24" steel casing pipe by method of bore and jack in lengths of 235' and 174' respectively, two railroad spur line crossings with 16" steel casing pipe installed by method of bore and jack and open cut totaling 168' and all related work associated with the completion of the project.

1.03 PROJECT TIME

- A. Contractor agrees that the work will be completed and ready for final payment in accordance with Paragraph 12.2 of the General Conditions directed after the date the Contract Time commences to run. Contract Time shall be 150 consecutive calendar days to Substantial Completion and 180 consecutive calendar days to Final Completion.

1.04 GENERAL REQUIREMENTS

- A. Smoking and Fire Precautions: No smoking, fire, or use of any fire or explosion producing tools or equipment shall be permitted on the premises or at any locations where such may endanger said premises or the current operations thereon.
- B. Manufacturers Qualifications: The manufacturers of all materials and equipment used must be reputable and regularly engaged in the manufacture of the particular material or equipment for the use and service to which it will be subjected.
- C. Contractor Shall Pay for All Laboratory Inspection Service: All materials and equipment used in the construction of the project shall be subject to adequate inspection and testing in accordance with accepted standards. The laboratory or inspection agency shall be selected by the Contractor and approved by the Engineer and/or Owner. Contractor to pay for all laboratory inspection services as a part of the Contract. Submit all material test reports to the Owner in triplicate.

- D. Compliance With State and Local Laws: Comply with all applicable requirements of state and local laws and ordinances to the extent that such requirements do not conflict with federal laws or regulations.
- E. Protection of Public and Private Property: Take special care in working areas to protect public and private property. The contractor shall replace or repair at his own expense any damaged water pipes, power and communication lines, or other public utilities, roads, curbs, gutters, sidewalks, drain pipes, ponds or pond structures, sewer drainage ditches, all properties and fixtures (both permanent and temporary) fences, and all plantings, including grass or sod on the site of the work. Leave the site in original or better condition after all cleanup work has been done.
- Reasonable care shall be taken during construction to avoid damage to vegetation. Ornamental shrubbery and tree branches shall be temporarily tied back, where appropriate, to minimize damage. Trees which receive damage to branches shall be trimmed of those branches to improve the appearance of the tree. Tree trunks receiving damage from equipment shall be treated with a tree dressing.
- F. Sewer Bypassing or Overflows: No wastewater bypassing shall occur during construction unless a schedule has been approved by the Division of Water and/or by EPA/NEPA permit if required.
- G. Markers: Preserve all USGS, TVA, and State property markers and private markers. Do not remove or disturb any such markers without prior approval from the Owner. Any removal and replacement of such markers shall be at the expense of the Contractor.
- H. Non-discrimination: The Contractor agrees to hire qualified persons without regard to race, creed, color, sex, or national origin for the performance of the work specified in this contract.
- I. Pavement Repair and/or Replacement: Whenever pipe trenches are cut across or along existing pavement or shoulders, backfill same and restore traffic over the cuts as quickly as possible by constructing a temporary surface with twelve (12) inches of Class A, grade D crushed stone. Add material and otherwise maintain such surface until the permanent pavement is restored by the Contractor or until the entire project is accepted.
- J. Highway Department Permits: The Owner shall secure any permits and provide bond as required by the Tennessee Department of Transportation or Maury County, Tennessee for the installation of permanent facilities on highway rights-of-way. All such work shall be coordinated with and be subject to the approval of TDOT.
- K. Approved Chemicals: All chemicals used during project construction or furnished for project operation, whether herbicide, pesticide, disinfectant, polymer, reactant,

or of other classification, must show approval of either EPA or USDA. The use of all such chemicals and the disposal of residues shall be in strict conformance with instructions.

- L. Catalogue Data for Owners: Provide duplicate, complete, bound sets of a compilation of catalog data of each manufactured item of mechanical and electrical equipment used in the work, and present this compilation to the Engineer for transmittal to the Owner before payment of more than ninety percent (90%) is made. Include descriptive data and printed installation, operating, and maintenance instruction (including a parts list for each item of equipment) Provide a complete double index as follows:
1. Listing the products alphabetically by name.
 2. Listing alphabetically the names of manufacturers whose products have been incorporated in the work, together with their addresses and the names and addresses of the local sales representative.
- M. Operation and Maintenance Instruction to Owner: Where the specifications for specific equipment require that a factory service representative provide operation and maintenance instruction to the Owner for that equipment, this service is to be performed by prior arrangement with the Owner after and in addition to the manufacturer's instructions to the Contractor for installation and start-up. The individual performing the instruction to the Owner shall be trained and/or certified by the manufacturer as its authorized operation, maintenance, and service specialist. If the said specialist is not a regular full-time employee of the manufacturer, the specialist's qualifications shall be submitted to the Owner for review and approval prior to scheduling the site visit for instructions to the Owner.
- N. Contractor shall update maps based on the evaluation work. Any discrepancy between manhole locations and/or line segment connections shall be noted on the plans. Contractor will be provided with a sufficient number of sets of plans to clearly and legibly show any revisions or changes.

Additionally, Contractor shall maintain an "up to date" set of As-Built Drawings. This set shall clearly identify the type of work performed, sewer line lengths, manhole invert elevations, location of service reconnections and any other information pertinent to the completion of the project.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

Not Used

END OF SECTION