

SECTION 01010

PROJECT SUMMARY

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Summary of the Work
- B. Project Time
- C. General Requirements

1.02 SUMMARY OF THE WORK

- A. This project consists of:
 - 1. The installation of approximately 16,300 linear feet of 36-inch water transmission main to carry water from the Decatur Utilities water system to a pump station within the Limestone County Water and Sewer Authority water system including valves and all related items.
 - 2. Installation of the 36-inch water line can summarized as follows:
 - a. Approximately 400 linear feet of open-cut install within public right-of-way and easements within the City of Decatur
 - b. Approximately 2,700 linear feet of HDD installation under the Tennessee River
 - c. Approximately 5,600 linear feet of subaqueous installation within Wheeler Lake
 - d. Approximately 3,375 linear feet of open-cut, bore and jack and HDD installation within the Decatur Day Park and railroad right-of-way.
 - e. Approximately 4,225 linear feet of open-cut installation within private easements to proposed LCWSA Booster Station
 - 3. Installation of approximately 600 linear feet of 36-inch and 125 lf of 16-inch water line along Sandy Road to carry water from the proposed Water Booster Station to the existing distribution system.

1.03 PROJECT TIME

- A. Contractor agrees that the work will be completed and ready for final payment in accordance with Paragraph 12.2 of the General Conditions directed after the date

the Contract Time commences to run. Contract Time shall be 540 consecutive calendar days to Final Completion.

1.04 GENERAL REQUIREMENTS

- A. Smoking and Fire Precautions: No smoking, fire, or use of any fire or explosion producing tools or equipment shall be permitted on the premises or at any locations where such may endanger said premises or the current operations thereon.
- B. Manufacturers Qualifications: The manufacturers of all materials and equipment used must be reputable and regularly engaged in the manufacture of the particular material or equipment for the use and service to which it will be subjected.
- C. Contractor Shall Pay for All Laboratory Inspection Service: All materials and equipment used in the construction of the project shall be subject to adequate inspection and testing in accordance with accepted standards. The laboratory or inspection agency shall be selected by the Contractor and approved by the Engineer and/or Owner. Contractor to pay for all laboratory inspection services as a part of the Contract. Submit all material test reports to the Owner in triplicate.
- D. Compliance With State and Local Laws: Comply with all applicable requirements of state and local laws and ordinances to the extent that such requirements do not conflict with federal laws or regulations.
- E. Protection of Public and Private Property: Take special care in working areas to protect public and private property. The contractor shall replace or repair at his own expense any damaged water pipes, power and communication lines, or other public utilities, roads, curbs, gutters, sidewalks, drain pipes, ponds or pond structures, sewer drainage ditches, all properties and fixtures (both permanent and temporary) fences, and all plantings, including grass or sod on the site of the work. Leave the site in original or better condition after all cleanup work has been done.
- F. Markers: Preserve all USGS, TVA, and State of Alabama property markers and private markers. Do not remove or disturb any such markers without prior approval from the Owner. Any removal and replacement of such markers shall be at the expense of the Contractor.
- G. Non-discrimination: The Contractor agrees to hire qualified persons without regard to race, creed, color, sex, or national origin for the performance of the work specified in this contract.
- H. Pavement Repair and/or Replacement: Whenever pipe trenches are cut across or along existing pavement or shoulders, backfill same and restore traffic over the

cuts as quickly as possible by constructing a temporary surface with twelve (12) inches of Class A, grade D crushed stone. Add material and otherwise maintain such surface until the permanent pavement is restored by the Contractor or until the entire project is accepted.

- I. Department of Transportation Permits: The Owner shall secure any permits and provide bond as required by the Alabama Department of Transportation, City of Decatur, or Limestone County, Alabama for the installation of permanent facilities on highway rights-of-way. All such work shall be coordinated with and be subject to the approval of the Department of Transportation.
- J. Tunneling or Boring: Where the drawings show that utilities are to be tunneled or bored, the linear foot amount shown in the Bid Form includes the carrier pipe, steel casing pipe, and all other items of work necessary for the line to be completely installed under the railroad or public roads as shown. The boring shall be accomplished by means of augering to the size, line, and grade shown on the drawings.
- K. Approved Chemicals: All chemicals used during project construction or furnished for project operation, whether herbicide, pesticide, disinfectant, polymer, reactant, or of other classification, must show approval of either EPA or USDA. The use of all such chemicals and the disposal of residues shall be in strict conformance with instructions
- L. Catalogue Data for Owners: Provide duplicate, complete, bound sets of a compilation of catalog data of each manufactured item of mechanical and electrical equipment used in the work, and present this compilation to the Engineer for transmittal to the Owner before payment of more than ninety percent (90%) is made. Include descriptive data and printed installation, operating, and maintenance instruction (including a parts list for each item of equipment) Provide a complete double index as follows:
 - 1. Listing the products alphabetically by name.
 - 2. Listing alphabetically the names of manufacturers whose products have been incorporated in the work, together with their addresses and the names and addresses of the local sales representative.
- M. Operation and Maintenance Instruction to Owner: Where the specifications for specific equipment require that a factory service representative provide operation and maintenance instruction to the Owner for that equipment, this service is to be performed by prior arrangement with the Owner after and in addition to the manufacturer's instructions to the Contractor for installation and start-up. The individual performing the instruction to the Owner shall be trained and/or certified by the manufacturer as its authorized operation, maintenance, and service specialist. If the said specialist is not a regular full-time employee of the manufacturer, the specialist's qualifications shall be submitted to the Owner for

review and approval prior to scheduling the site visit for instructions to the Owner.

- N. Drawings of Record: Provide a complete, up-to-date record set of drawings, which shall be corrected daily to show every change to the approved shop drawings and shall be deducted from any amounts that are due or become due to the Contractor. Contractor is responsible for providing a field survey (including HDD path) of the installed water line that meets TVA Professional Land Survey Requirements to LCWSA at completion of construction.
- O. Preservation of Existing Vegetation: Take reasonable care during construction to avoid damage to vegetation. Where the area to be excavated is occupied by trees, brush, or other uncultivated vegetable growth, clear such growth from the area, as needed to install the work and dispose of it in a satisfactory manner. Wholesale clearing will not be allowed. Leave undisturbed any trees, cultivated shrubs, flowers, etc., situated within public rights-of-way and/or easements through private property but not located directly within excavation limits. Transplant small ornamental trees, cultivated shrubs, flowers, etc., located directly within excavation limits so they may be replaced during property restoration operations. Do not remove or disturb any tree larger than 6 inches in diameter without the permission of the Engineer. Take special precautions (including the provision of barricades and the temporary tying back of shrubbery and tree branches) for the protection and preservation of such objects throughout all stages of construction; the Contractor will be held liable for any damage that may result to said objects from excavation or construction operations. Trim any limbs or branches of trees broken during construction operations with clean cut, and paint with an approved tree pruning compound. Treat tree trunks receiving damage from equipment with a tree dressing.
- No trees shall be removed from the Decatur Day Park (TVA property). When necessary to clear trees within the easements, trees shall remain where fallen or sidecast (not stacked). The Contractor is responsible for keeping a record of all hardwood trees 3-caliper inch and larger that are removed from the temporary construction easement within wetland areas. The trees shall be documented by type and size and this record shall be given to the Authority at completion of construction.
- P. Utilities: The Contractor is to contact the Owner of all underground utilities before beginning construction in the area. Carefully protect from damage all utilities in the vicinity of the work at all times. If it is necessary to repair, remove, and/or replace any such utility in order to complete the work properly, do so in compliance with the rules and regulations of the particular utility involved. Any such work shall be considered incidental to the construction of repairs of utility lines, and no additional payment will be allowed therefore.

PART 2 - PRODUCTS
N/A

PART 3 - EXECUTION
N/A

END OF SECTION