

SECTION 01010

PROJECT SUMMARY

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Summary of the Work
- B. Project Time
- C. General Requirements

1.02 RELATED SECTIONS

- A. Section 09870 – Steel Tank Rehabilitation
- B. Section 09873 – Steel Water Tank Coating Systems
- C. Section 13421 – Disinfection of Water Storage Facilities

1.03 SUMMARY OF THE WORK

- A. This project consists of Painting and Rehabilitation of one (1) existing water storage tank. Tank name and size is as follows:
 - 1. 100,000 gallon Elevated Blue Tank
- B. This is a NO-PLANS contract.
- C. For general existing tank information refer to the tank inspection report located in the Appendix.

1.04 GENERAL REQUIREMENTS

- A. Smoking and Fire Precautions: No smoking, fire, or use of any fire or explosion producing tools or equipment shall be permitted on the premises or at any locations where such may endanger said premises or the current operations thereon.
- B. Manufacturers Qualifications: The manufacturers of all materials and equipment used must be reputable and regularly engaged in the manufacture of the particular material or equipment for the use and service to which it will be subjected.

- C. Contractor Shall Pay for All Laboratory Inspection Service: All materials and equipment used in the construction of the project shall be subject to adequate inspection and testing in accordance with accepted standards. The laboratory or inspection agency shall be selected by the Contractor and approved by the Engineer and/or Owner. Contractor to pay for all laboratory inspection services as a part of the Contract. Submit all material test reports to the Owner in triplicate.
- D. Compliance With State and Local Laws: Comply with all applicable requirements of state and local laws and ordinances to the extent that such requirements do not conflict with federal laws or regulations.
- E. Protection of Public and Private Property: Take special care in working areas to protect public and private property. The contractor shall replace or repair at his own expense any damaged structures or vehicles damaged by the painting work and all plantings, including grass or sod on the site of the work. Leave the site in original or better condition after all cleanup work has been done.
- F. Markers: Preserve all USGS, TVA, State of Tennessee, County property markers, and private markers. Do not remove or disturb any such markers without prior approval from the Owner. Any removal and replacement of such markers shall be at the expense of the Contractor.
- G. Non-discrimination: The Contractor agrees to hire qualified persons without regard to race, creed, color, sex, or national origin for the performance of the work specified in this contract.
- H. Approved Chemicals: All chemicals used during project construction or furnished for project operation, whether herbicide, pesticide, disinfectant, polymer, reactant, or of other classification, must show approval of either EPA or USDA. The use of all such chemicals and the disposal of residues shall be in strict conformance with instructions
- I. Preservation of Existing Vegetation: Take reasonable care during construction to avoid damage to vegetation. Where the area to be excavated is occupied by trees, brush, or other uncultivated vegetable growth, clear such growth from the area, and dispose of it in a satisfactory manner. Leave undisturbed any trees, cultivated shrubs, flowers, etc., situated within public rights-of-way and/or easements through private property but not located directly within excavation limits. Transplant small ornamental trees, cultivated shrubs, flowers, etc., located directly within excavation limits so they may be replaced during property restoration operations. Do not remove or disturb any tree larger than 6 inches in diameter without the permission of the Engineer. Take special precautions (including the provision of barricades and the temporary tying back of shrubbery and tree branches) for the protection and preservation of such objects throughout all stages of construction; the Contractor will be held liable for any damage that may result

to said objects from excavation or construction operations. Trim any limbs or branches of trees broken during construction operations with clean cut, and paint with an approved tree pruning compound. Treat tree trunks receiving damage from equipment with a tree dressing.

- J. Utilities: The Contractor is to contact the Owner of all underground utilities before beginning construction in the area. Contractor shall determine exact location of all existing utilities prior to beginning construction in accordance with *State of Tennessee, Title 65 – Public Utilities and Carrier, Chapter 31 Underground Utility Damage Prevention Act*. Carefully protect from damage all utilities in the vicinity of the work at all times. If it is necessary to repair, remove, and/or replace any such utility in order to complete the work properly, do so in compliance with the rules and regulations of the particular utility involved. Any such work shall be considered incidental to the construction of repairs of utility lines, and no additional payment will be allowed therefore.

- K. If previously unevaluated archaeological resources, features, or artifacts are discovered during project construction, the Contractor shall immediately cease work and contact the Engineer. The Engineer will contact the appropriate governing agencies to determine what further action, if any, will be necessary to comply with specific requirements of the agencies.

PART 2 - PRODUCTS

N/A

PART 3 - EXECUTION

N/A

END OF SECTION