

## SECTION 01010

### PROJECT SUMMARY

#### PART 1 - GENERAL

##### 1.01 SECTION INCLUDES

- A. Summary of the Work
- B. Project Time
- C. General Requirements

##### 1.02 SUMMARY OF THE WORK

- A. This project consists of:
  - 1. The insertion of a new 18-inch gate valve in the existing water line at a location just west of Nissan USA headquarters.
  - 2. Replacement of the existing meter assembly at Legends Golf Course including improvements to the meter box.
  - 3. Demolition of the existing Jordan Road Water Pump Station.
  - 4. A new control valve assembly at the Jordan Road site.
  - 5. A new control valve assembly at the Sliders Knob tank site.
  - 6. A new meter pit and control valve located on Moores Lane to serve Nolensville/College Grove Utility District.
- B. Three (3) allowances have been included in this project for Brann & Whittemore, Inc. to provide instrumentation services specifically described in Section 11290, Section 11291 and Section 11311 of this construction manual. Brann & Whittemore, Inc. shall provide, install, and start-up as outlined in each of the respective specification sections. State sales tax has been included in the allowances.

##### 1.03 PROJECT TIME

- A. The project time shall be 150 consecutive calendar days for Substantial Completion and 160 consecutive calendar days for Final Completion to complete the work as shown on the Contract Documents.

##### 1.04 GENERAL REQUIREMENTS

- A. Smoking and Fire Precautions: No smoking, fire, or use of any fire or explosion producing tools or equipment shall be permitted on the premises or at any

locations where such may endanger said premises or the current operations thereon.

- B. **Manufacturers Qualifications:** The manufacturers of all materials and equipment used must be reputable and regularly engaged in the manufacture of the particular material or equipment for the use and service to which it will be subjected.
- C. **Contractor Shall Pay for All Laboratory Inspection Service:** All materials and equipment used in the construction of the project shall be subject to adequate inspection and testing in accordance with accepted standards. The laboratory or inspection agency shall be selected by the Contractor and approved by the Engineer and/or Owner. Contractor to pay for all laboratory inspection services as a part of the Contract. Submit all material test reports to the Owner in triplicate.
- D. **Compliance With State and Local Laws:** Comply with all applicable requirements of state and local laws and ordinances to the extent that such requirements do not conflict with federal laws or regulations.
- E. **Protection of Public and Private Property:** Take special care in working areas to protect public and private property. The contractor shall replace or repair at his own expense (unless otherwise specified) any damaged water pipes, power and communication lines, or other public utilities, roads, curbs, gutters, sidewalks, drain pipes, ponds or pond structures, sewer drainage ditches, all properties and fixtures (both permanent and temporary), fences, and all plantings, including grass or sod on the site of the work. Leave the site in original or better condition after all cleanup work has been done.
- F. **Markers:** Preserve all USGS, TVA, State of Tennessee, Williamson County, City of Brentwood property markers and private markers. Do not remove or disturb any such markers without prior approval from the Owner. Any removal and replacement of such markers shall be at the expense of the Contractor.
- G. **Non-discrimination:** The Contractor agrees to hire qualified persons without regard to race, creed, color, sex, or national origin for the performance of the work specified in this contract.
- H. **Pavement Repair and/or Replacement:** Whenever pipe trenches are cut across or along existing pavement or shoulders, backfill same and restore traffic over the cuts within 7 days with binder replacement. Trench plates shall be used until pavement replacement is completed. All backfill and paving requirements shall be in accordance with City of Franklin and/or the City of Brentwood standards.
- I. **Department of Transportation Permits:** The Owner shall secure any permits and provide bond as required by the Tennessee Department of Transportation, City of Franklin or City of Brentwood for the installation of permanent facilities on

highway rights-of-way. All such work shall be coordinated with and be subject to the approval of the Department of Transportation, the County, Franklin and/or Brentwood.

- J. Approved Chemicals: All chemicals used during project construction or furnished for project operation, whether herbicide, pesticide, disinfectant, polymer, reactant, or of other classification, must show approval of either EPA or USDA. The use of all such chemicals and the disposal of residues shall be in strict conformance with instructions
- K. Drawings of Record: Provide a complete, up-to-date record set of blue line prints, which shall be corrected daily to show every change to the approved shop drawings and shall be deducted from any amounts that are due or become due to the Contractor.
- L. Preservation of Existing Vegetation: Take reasonable care during construction to avoid damage to vegetation. Where the area to be excavated is occupied by trees, brush, or other uncultivated vegetable growth, clear such growth from the area, and dispose of it in a satisfactory manner. Leave undisturbed any trees, cultivated shrubs, flowers, etc., situated within public rights-of-way and/or easements through private property but not located directly within excavation limits. Transplant small ornamental trees, cultivated shrubs, flowers, etc., located directly within excavation limits so they may be replaced during property restoration operations. Do not remove or disturb any tree larger than 6 inches in diameter without the permission of the Engineer. Take special precautions (including the provision of barricades and the temporary tying back of shrubbery and tree branches) for the protection and preservation of such objects throughout all stages of construction; the Contractor will be held liable for any damage that may result to said objects from excavation or construction operations. Trim any limbs or branches of trees broken during construction operations with a clean cut at the trunk of the tree, and paint with an approved tree pruning compound. Treat tree trunks receiving damage from equipment with a tree dressing.
- M. Utilities: The Contractor is to contact the Owner of all underground utilities before beginning construction in the area. Contractor shall determine exact location of all existing utilities prior to beginning construction in accordance with *State of Tennessee, Title 65 – Public Utilities and Carrier, Chapter 31 Underground Utility Damage Prevention Act*. Carefully protect from damage all utilities in the vicinity of the work at all times. If it is necessary to repair, remove, and/or replace any such utility in order to complete the work properly, do so in compliance with the rules and regulations of the particular utility involved. Any such work shall be considered incidental to the construction of repairs of utility lines, and no additional payment will be allowed therefore.

**PART 2 - PRODUCTS**

N/A

**PART 3 - EXECUTION**

N/A

**END OF SECTION**